

GENERAL NOTES

1. EXISTING FIELD CONDITIONS MAY VARY FROM CONDITIONS ANTICIPATED DURING PREPARATION OF THESE DOCUMENTS. IF CONDITIONS VARY AND WARRANT FURTHER RESEARCH AND IDENTIFICATION OF SUBSEQUENT ISSUES, NOTIFY THE OWNER AND ARCHITECT IMMEDIATELY.
2. SEE SHEETS G1007 WALL TYPES.
3. CONTRACTOR IS RESPONSIBLE TO COORDINATE ALL WORK. WHEN CONFLICT ARISES, NOTIFY THE ARCHITECT IMMEDIATELY.
4. PROVIDE BACKING FOR ALL FIXTURES.
5. PROVIDE BACKING FOR FUTURE WALL MOUNTED GRAB BARS AT WATER CLOSETS, TUBS AND SHOWERS IN UNITS ON GROUND LEVEL. AT WATER CLOSET LOCATIONS WHERE STANDARD GRAB BARS ARE NOT FEASIBLE BACKING SHALL BE PROVIDED FOR SWING UP GRAB BARS. (REFER TO ANSI 1004.11.1.1 FOR SWING UP GRAB BAR REQUIREMENTS)
6. ALL CABINETY UNDER LAVATORIES IN ALL UNIT BATHROOMS ON THE GROUND LEVEL ARE REQUIRED TO FOLLOW THE FOLLOWING GUIDELINES: (i) THE CABINETY SHALL BE ABLE TO BE REMOVED WITHOUT REMOVAL OR REPLACEMENT OF THE LAVATORY; (ii) THE FLOOR FINISH SHALL EXTEND UNDER THE CABINETY; (iii) THE WALLS BEHIND AND SURROUNDING THE CABINETY SHALL BE FINISHED.
7. SEE ENLARGED UNIT PLANS FOR UNIT DIMENSIONS, WALL TYPES & DOOR TYPES.
8. REFER TO WINDOW TYPES FOR WINDOW SLIDE DIRECTION AT OPERABLE WINDOWS.

KEYNOTES		
5.02	STEEL AWNING.	
5.03	STEEL CHANNEL CONCRETE TREAD STAIRS.	
10.05	FIRE EXTINGUISHER IN SEMI-RECESSED CABINET. SEE SPEC.	
21.01	FIRE RISER.	

Legend			
	Description	Quantity	Unit
✓	Unit 2	4	Count
✓	Unit 3	4	Count

