DOOR SCHEDULE

	DOOR No.	ROOM	DOOR TYPE	FRAME TYPE	WIDTH	HEIGHT	ELEVATION	HARDWARE SET	FIRE RATING	COMMENTS
THIRD FL.	301F	CORRIDOR	SWC/GL	HM	2'-10"	7'-0"	C	SET 11.0		CARD READER
THIRD FL.	309	SUPERINTENDENT OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 15.0		
THIRD FL.	309A	TL.	SCW	HM	3'-0"	7'-0"	A	SET 35.0		ALTERNATE BID, TOILET ROOM TO HAVE 3/4" UNDERCUT
THIRD FL.	309B	CL.	SCW	HM	3'-0"	7'-0"	A	SET 20.0		
THIRD FL.	310	NP DIRECTORS OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	312	SUPERVISOR OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	314	SUPERVISOR OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	316	BOOKEEPER OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	318	SPEECH CONF. RM.	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	320	NP SPEECH OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	322	NP SECRETARY	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	324A	TRANSPORTATION OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		
THIRD FL.	324B	TRANSPORTATION OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 18.0		
THIRD FL.	325	BREAK OUT ROOM	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		BASE BID: CARD READER, ALTERNATE BID: DOOR REPLACEMENT
THIRD FL.	326	TRANSPORTATION OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 15.0		
THIRD FL.	327	IT RM.	SCW	HM	3'-0"	7'-0"	A	SET 41.0		BASE BID: CARD READER, ALTERNATE BID: DOOR REPLACEMENT
THIRD FL.	331	NP FILE RM.	SCW	HM	3'-0"	7'-0"	A	SET 41.0		ALTERNATE BID
THIRD FL.	332A	TRANSPORTATION OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 15.0		
THIRD FL.	332B	TRANSPORTATION OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 18.0		
THIRD FL.	333	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	334	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	335	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	336	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	337	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	338	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	339	NP STG	SCW	HM	3'-0"	7'-0"	A	SET 41.0		ALTERNATE BID
THIRD FL.	340	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	341A	CL.	SCW	HM	4'-5"	7'-0"	I	SET 41.0		ALTERNATE BID
THIRD FL.	342	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	344	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	345	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	346	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	347	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	348	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	348A	PROFESSIONAL LEARNING SPACE	SWC/GL	HM	2'-10"	7'-0"	C	SET 36.0		
THIRD FL.	348B	PROFESSIONAL LEARNING SPACE	SWC/GL	HM	3'-0"	7'-0"	D	SET 37.0		
THIRD FL.	356	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 17.0		ALTERNATE BID
THIRD FL.	356.1	SUPERINTENDENT OFFICE	SCW	HM	3'-0"	7'-0"	C	SET 17.0		
THIRD FL.	356A	CL.	SCW	HM	5'-4"	7'-0"	I	SET 41.0		ALTERNATE BID
THIRD FL.	357	STG.	SCW	HM	3'-0"	7'-0"	A	SET 41.0		ALTERNATE BID
THIRD FL.	357A	LOBBY	SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		
THIRD FL.	357B		SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		
THIRD FL.	358	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	360	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	362	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	363A	SUPERINTENDENT CONFERENCE RM.	SWC/GL	HM	3'-0"	7'-0"	C	SET 41.0		BASE BID: CARD READER, ALTERNATE BID: DOOR REPLACEMENT
THIRD FL.	363B	SUPERINTENDENT CONFERENCE RM.	SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		BASE BID: CARD READER, ALTERNATE BID: DOOR REPLACEMENT
THIRD FL.	364	CORRIDOR	SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		CARD READER
THIRD FL.	366	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		CARD READER
THIRD FL.	367	OFFICE	SWC/GL	HM	3'-0"	7'-0"	C	SET 10.0		CARD READER
THIRD FL.	367A	UTILITY RM.	SCW	HM	6'-0"	7'-0"	I	SET 42.0		
THIRD FL.	368	W. TL.	SCW	HM	3'-0"	7'-0"	A	SET 30.0		ALL TOILET AND SHOWER ROOMS TO HAVE 3/4" UNDERCUT
THIRD FL.	369	M. TL.	SCW	HM	3'-0"	7'-0"	A	SET 30.0		ALL TOILET AND SHOWER ROOMS TO HAVE 3/4" UNDERCUT
THIRD FL.	369A	CORRIDOR	SCW	HM	2'-4"	7'-0"	A1	SET 24.0		
THIRD FL.	371	NP COPY RM.	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID
THIRD FL.	372	NP SECRETARY	SWC/GL	HM	3'-0"	7'-0"	C	SET 40.0		ALTERNATE BID

3/10/2026 3:27:20 PM C:\Users\ShannonW\Documents\25.138B - 53 Cardinal Building Alteration - 2026.02.26_ShannonwQ8LDL.rvt

SOLUTIONS
ARCHITECTURE
FRANK A. MESSINEO, AIA ▪ AI14580

NOT VALID FOR CONSTRUCTION
UNLESS SIGNED BY THE ARCHITECT

This document and all others contained herein are the property and copyright of Solutions Architecture, LLC for use on the specified project and shall not be used or reproduced without the express written consent of the Architect

96 Pompton Avenue 2nd Floor, Suite 200 Verona, NJ 07044
o 973.484.4800 f 201.706.7777
e info@solutions-arch.com www.solutions-arch.com

Architect's Seal:

INTERIOR ALTERATIONS
FOR
UNION COUNTY EDUCATIONAL SERVICES COMMISSION
AT
WESTLAKE / UCESC BOE
53 CARDINAL DR., WESTFIELD, NEW JERSEY 07090

Consulting Engineer's Seal:

DOOR SCHEDULES

No.	DATE:	COMMENTS:
	03/10/26	ISSUE FOR BID

DATE: 3/10/2026
SCALE:
SOLUTION No. **25.138B**
DRAWN BY: SW, JR
CHECKED BY: VO
DRAWING No. **A.5.1**